





CHARLIE
TYPE

C.2
VARIANT

VIRTUES

Charlie explores an optimized structural system comprised of columns, beams and hollow-core plank which can easily expand or contract in a longitudinal, transverse or vertical direction. The design strikes a balance between repetition and variation, creating value through economy and experience.

A daylight strategy guides the expression of form and space, with a variety of apertures in the roof and wall planes. Elevated roof monitors are syncopated with internal courtyards to extend the formal and spatial dynamic of the building.

Enclosure on the long east and west sides is comprised of insulated spandrel panels. They are smooth in texture and oriented with a strong vertical bias. Gently curved vertical fins on the first story project out beyond the glazing apertures to minimize solar gain while creating dynamic shadow play. A curved shadow hood protects recessed glazing on the second story.

Enclosure on the short north and south sides has a horizontal bias created by insulated spandrel panels. The south main entry is through a deep porch, while the north side has a flush face with a recessed service dock.

SPECIFICATIONS


Building Footprint: 140 feet by 286 feet = 40,040 square feet

Structural Bay Size: 20 feet (beam span) by 26 feet (plank span), column-free space


Building Height: 14 foot floor-to-floor height. Two stories at 28 feet, with monitors at 42 feet total height

Area of Precast Elements: 96,044 square feet of structure and thermal enclosure


Enclosure Glazing Ratio: 21% of total thermal enclosure







FINITE ELEMENTS



PRECAST
PROTOTYPES









